# POLICE STATION WINDOWS REPLACEMENT: ITB NO: 13-003
# Addendum No.1

June 11, 2013

The information contained in this Addendum modifies, supplements, or replaces information contained in the Bid Documents and is hereby made a part of the Contract Documents.

The non-mandatory Pre Bid Meeting, was held June 4, 2013 at 10 AM
as scheduled in the bid documents.

The following items are clarifications, deletions, revisions, changes and modifications that change the original Contract Documents only in the amount and to the extent hereinafter specified as ADDENDUM NO.1.

1. Question: Alternate #2 calls for bullet proof glazing at window types C and D. What level of protection is required?

   Level 2 protection is required. This results in specialized laminated glazing that is approximately 1" thick.

2. Question: What are the limits of painting around replacement windows and new work including feathered E.I.F.S finish, interior and exterior?

   Assume that the exterior finishing (feather into existing and new paint) will require 12" around (4 sides) each opening in addition to the new sand finish stucco surround detailed in the drawings. Match existing color and texture and provide a field sample installation for review by the owner and Architect.
   .
   The interior has new wood trim: returns and face trim at each opening. This allows for cutting out the gyp. board and covering the edge without painting the interior walls unless deteriorated (water damaged) gyp. bd. is encountered.

   Provide a UNIT PRICE per square yard to remove damaged gyp. bd. from existing metal furring, replace with new matching material (5/8") and finish (tape, float and paint)

Additional items of clarification;

Typical window head detail 2/A-2 calls for a saw cut and 24 ga. flashing across the tops of all window openings, with weeps. Weeps shall be 2" wide. There shall be 2 per window segment (4 weeps at a double window etc.) Weeps shall be placed symmetrically and will be included in the field sample installation discussed above.

**Attachments;**
**Pre Bid Attendees List**

All other items remain as called for in the documents.
End of Addendum No. 1

Police Station Windows 6-4-13

**SIGN-IN SHEET**

| NAME | COMPANY | PHONE/FAX | EMAIL |
|---|---|---|---|
| Pablo Arcia | ABC Const. | 305-663 03 22<br>305-267-2403 | Kwelo@ABCconstruction.cc |
| Moises Bichachi | ELCI CONSTRUCTION | 305-891-7990<br>305-891-7993 | moises@elciconstruction.com |
| Roy Lovell | Gary The Carpenter | 305 292 0261<br>305 292 2225 | garythecarpenter@hotmail |
| Brad Hager | Royal Crest | 305-735-4042 | brad@royal-crest.com |
| CHRISTIAN BRISSON | PEDRO FALCON ELECT. CONT. | 305-872-2200<br>2219 | cbbpk@bellsouth.net |
| Ken Bygler | Pedro Falcon | 305-872-2200<br>2219 | Kenbygler@bellsouth.net |
| FRANK HERDLISKA | W.P. Hoen Arch. | 305-296-8352 | |
| BILL HOHN | WP HOHN ARCH. | 296-8352 | WPHOHN@AOL.COM |
| LES MOUZON | TAGARELLI Const. | 813 380 5510<br>813 626 2951 | LMOUZON@ME.COM |
| Zack Nichols | Manley deBoer Lumber | 305-304-2901 | Zack@ManleydeBoer.com |
| Rick Williams | CSI Construction | 888-931-0125 | VVAINO@ constructionspecialists.com |

**SIGN-IN SHEET**

| NAME | COMPANY | PHONE/FAX | EMAIL |
|---|---|---|---|
| CRAIG OVERHOLT | OVERHOLT CONSTRUCTION | 305-234-9677 Ph. | coverholt@overholtcc.com |
| Rachel Bashore | Bella Construction | 3052929886<br>3052929880 | Rachel@concretebella.com |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |