



THE CITY OF KEY WEST

Post Office Box 1409
Key West, FL 33041-1409

ADDENDUM NO. 2 ITB 15-013 PROJECT CE1002 - CEMETERY SEXTON'S HOUSE

This addendum is issued as supplemental information to the bid package for clarification of certain matters of both a general and a technical nature. The referenced bid package is hereby addended in accordance with the following items:

1. **Lintels at Typical CMU Wall Openings**, in lieu of constructing wall openings as shown on drawing A5's various building sections. - All exterior CMU wall opening lintels with exception to the front door shall be constructed of cast-in-place concrete with a minimum of 8" bearing on each side of wall opening. Lintels shall be reinforced with 2 - #4 reinforcing steel bottom horizontal bars tied to vertical #4 bars with a minimum of 40d development length on each side of wall openings and #3 stirrups at 10" on center reaching from Tie Beam TB-1 top horizontal bars to lintel bottom horizontal bars. Lintels to be cast-in place monolithically with Tie-Beam TB-1.
2. **Lintel at Front Door CMU Wall Opening** - The lintel above front door arched transom shall be cast-in-place concrete with a minimum of 16" bearing on each side of wall opening. This cast-in-place arch shall extend from the closest CMU joint at or below the spring line up to the top of Tie Beam TB-1. Additionally, this cast-in-place arch shall be reinforced with 2 - #4 reinforcing steel bars placed diagonally on either side of arch and tied to vertical #4 bars with a minimum of 40d development length on each side of wall opening. This cast-in-place concrete arch lintel shall be placed monolithically with Tie-Beam TB-1.

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 2 by submitting the addendum with their proposal. Proposals submitted without acknowledgement or without this Addendum may be considered non-responsive.

Signature

Name of Business