



NOTES:
 SEE PLAN FOR C.T. HEIGHTS OF
 GEOMETRIC ARRANGEMENTS.
 ALL OTHER AREAS SHALL BE
 PLANTED AT RANDOM HEIGHTS.

TIE OUTER FRONDS WITH 3/16"
 HEMP (NO MORE THAN 6 WRAPS)

LEAVE A MINIMUM OF 6 FRONDS.
 CUTTING OF ALL FRONDS AND
 BUD WILL NOT BE ACCEPTED.

5 LAYERS OF BURLAP
 5 - 2" x 4" x 16" WOOD BATTEN
 CONNECTED WITH 2 - 3/4" STEEL
 BANDS

2" x 4" WOOD BRACE (3 MIN.)
 TOE NAIL TO BATTEN.
 ALL WOOD PRESSURE
 TREATED.

BACKFILL WITH
 NATIVE SOIL

36" x 36" DIA. BALL



City of Key West

Engineering Services
 3132 Flagler Avenue, Key West, FL 33040

TITLE
 TYPICAL PALM PLANTING/STAKING

DRAWN
 JTJ
 SCALE
 NTS

STANDARD DETAIL

JUL 2015
 DETAIL
 26